

# IPL Cochrane Extraction Plant – AEGS Yard Relocation



Client	Location	Project	Value
Inter Pipeline	Cochrane Extraction Plant	Alberta Ethane Gathering System (AEGS) Yard Relocation	\$630K
<b>Start Date:</b> August 2018		<b>Finish Date:</b> September 2018	
<p><b>Project Description:</b></p> <p>Project Goal: relocate existing pig receiver yard, owned by others, from its current location inside the plant to an area on the perimeter of the processing facilities.</p> <p>OCL's Scope: fabricate and install new process piping and structural to tie-in the new pig receiver yard (installed by others) to the existing facility.</p> <p><b>Project Statistics:</b></p> <ul style="list-style-type: none"> <li>▪ 400+ diameter weld inches of carbon pipe</li> <li>▪ 250+ diameter inches of stainless pipe</li> <li>▪ 80% of welding completed in the rack, 20% pre fab</li> <li>▪ 2 – 2" tie-in flanges</li> <li>▪ Ground disturbance in 3 locations within the plant</li> <li>▪ Install of 5 – 12" double helix and 5 – 8" single helix piles to 6m embed depth</li> <li>▪ 6,500+ kgs of structural fabricated and installed</li> <li>▪ 2100+ onsite manhours and 500+ shop manhours, 0 incidents</li> <li>▪ Completed on time, on budget, &lt;1% rework, 0 weld failures</li> </ul>		 	