

Inter Pipeline Reboiler Loop Mods



Client	Location	Project	Value
Inter Pipeline	Cochrane Extraction Plant	UNIT 2B REBOILER LOOP MODIFICATIONS	\$1.9M
Start Date: November 2013		Finish Date: June 2014	
<p>Project Description:</p> <ul style="list-style-type: none"> ▪ Replacement of cold boxes D-256D & D-254 / D-255B (D-254 & D-255 is one combination cold box) with the new cold boxes, to be tagged D-256D & D-254 / D-255B ▪ Replacement of the existing piping to and from the cold boxes with new larger diameter piping ▪ Replacement of the demethanizer tower (D-852B) nozzels with larger diameter nozzles ▪ Installation of new tray distributors and a baffle modification in D-852B ▪ Replacement of existing pipe supports and springs ▪ Replacement and/or modification of piping structural supports ▪ Installation of new structural steel foundation to be placed on existing pile foundations of D-254/255B ▪ Tie-in to existing piping systems ▪ Oversee scaffolding, E&I, insulation and fire proofing activities ▪ Develop and manage project scheduling 		<p>Project Statistics:</p> <ul style="list-style-type: none"> ▪ Took over management and procurement of materials from client ▪ 2336 diameter weld inches of stainless pipe ▪ 5100 KGS of structural fabricated and installed ▪ 6000+ on-site manhours and 1500 shop manhours ▪ 0 LTI'S, 0 MA's 	