

IPL Cochrane Extraction Plant



Client	Location	Project	Value
Inter Pipeline	Cochrane Extraction Plant	Unit 2B Tower Mods & Cold Box Installation	\$2M
Start Date: January 2014		Finish Date: May 2014	
<p>Project Description:</p> <p>IPL awarded project to OCL as a sub-contractor to upsize SS nozzles and piping on existing tower and install new cold boxes in unit 2B.</p> <ul style="list-style-type: none"> ▪ Completed 2363 diameter weld inches on 12", 14" & 16" SS piping ▪ Installed 2 new cold boxes ▪ OCL took over materials management from IPL, managed schedule ▪ OCL provided day to day direction to IPL's sub contractors (scaffolding, civil contractor, crane supplier, NDE crews and specialty welding contractor) ▪ Replacement of the existing piping to and from the cold boxes with new larger diameter piping ▪ Replacement of the demethanizer tower nozzels with larger diameter nozzles ▪ Installation of new tray distributors and a baffle modification ▪ Replacement, modification and tie-in of piping structural supports and springs ▪ Installation of new structural steel foundation on existing pile foundations ▪ Project finished on budget with zero LTI's 			