

Kearl Barge Relocation



Client	Location	Project	Value
Imperial Oil	Kearl Oilsands	Barge and Piping Relocation KEP / KID	\$2M
Start Date: July 2016		Finish Date: September 2016	
<p>Project Description:</p> <p>A time sensitive scope to relocate two (2) barges and associated piping.</p> <p>Pre-Shutdown</p> <ul style="list-style-type: none"> ▪ Construct crane pads ▪ Install new winches and structural steel on barge ▪ Prefabricate new piping <p>Shutdown</p> <ul style="list-style-type: none"> ▪ Construct crane pads ▪ Remove existing winches ▪ Demo and remove 48" ▪ Disconnect gangways ▪ Relocate piping and move barges ▪ Relocate concrete anchor pad ▪ 48" closure welds <p>Other activities</p> <ul style="list-style-type: none"> ▪ Coordinate schedule for all sub trades, electrical, heavy cranes, on water contractor, survey and geotechnical. 		 	