

# Syncrude Aurora/Base Plant Pipeline



Client	Location	Project	Value
North American	Syncrude Aurora/Base Plant	ICRFLR - ISBL 36" Pipeline	\$6M
<b>Start Date:</b> April 2016		<b>Finish Date:</b> December 2016	
<p><b>Project Description:</b></p> <p>This challenging CSA Z662 pipeline project required the installation of underground 36" piping through the heart of two operating oilsands plants.</p> <p><b>Aurora EWP 634</b></p> <ul style="list-style-type: none"> <li>▪ Hydro excavation &amp; daylighting of underground utilities</li> <li>▪ Fabrication, blasting, coating, installation of a 36" Froth line</li> <li>▪ Hydrotest, pig and dry the 36" 900 meters pipeline</li> </ul> <p><b>Base Plan EWP 635/639</b></p> <ul style="list-style-type: none"> <li>▪ Hydro excavation &amp; daylighting of underground utilities</li> <li>▪ Fabrication, blasting, coating, installation of a 36" Froth line</li> <li>▪ Fabrication, blasting, coating and installation of some 6", 8" 18" drain lines</li> <li>▪ Tie into the pig catcher and plant flanges</li> <li>▪ Hydrotest pig and dry the 36" 1.8km pipeline</li> <li>▪ Hydrotest of the 6", 8" and 18" lines</li> </ul>		 	